

**miscellaneous slides, status and
comments on:**

LHC (Beam 2) Commissioning

- BPM, Q, Q'

Instrumentation and Diagnostics -

**Ralph J. Steinhagen for the BI-QP team
Accelerator & Beams Department, CERN**

For those who have been nice...

- Tune Measurements
- Coupling Measurements
- Chromaticity estimates
 - Injection tune shifts
 - Q resonance width & Q_s side-bands

Something to think about/follow up...

- Residual LHC beam noise and misalignment estimates
 - BBQ and BPM resolution





- Three independent BBQ Tune/Coupling diagnostic chains available per beam:
 - **PLL based acquisition - commissioning pending!**
 - one measurement at high/reduced acquisition frequency, targets:
 - 100 Hz for feedbacks (driven by need to reduce feedback latencies)
 - 1 Hz for general purpose logging
 - expert: high frequency data, event synchronised and buffered (post-mortem, PLL setup), typical length: 5 min \leftrightarrow < 1 MB of data
 - main use: monitoring/logging, feedbacks, fill-to-fill studies, ...
 - **FFT based acquisition – 'periodic' (FFT1) – B2 fully commissioned**
 - one measurement every 1 second starting from first-injection
 - intended use: monitoring/logging, (feedbacks), fill-to-fill studies, ...
 - **FFT based acquisition – 'on demand' (FFT2) – B2 fully commissioned**
 - n-measurements synchronised to an external event (BPM, BQ, ...)
 - intended use: expert diagnostics, detailed studies, ...

Present Commissioning State

- BBQ systems for B2 including excitation and correction commissioned
 - One important stepping stone in getting the beams circulating

Very first turn B2 (B1 similar)!





first circulating beam...



- Next few slides document how we got there...
 - N.B. Colour coding: 'blue frames' = B1 data & 'red frames' = B2 data

Sep. 10th Beam 2 Injection Tune – 14 Turn Data




- After adjusting first two turns (no RF, $Q_H \approx .44$, $Q_V \approx .28$)
 - Transient in raw (turn-by-turn) data: BBQ intrinsic discharging once beam is gone





- Observations: only 14 turns – could the big spectra 'humps' indeed be the injection Q's?
 - vertical spectra is cleaner → decided to trim ' $\Delta q_v = -0.1$ ' and observe change

Beam 2 Injection Tune – 14 Turn Data – Q_V Trim

- no RF capture , $Q_H \approx .5 \rightarrow .315$, $Q_V \approx .24$, observation:
 - Programmed ' $\Delta Q_H = -0.2$ ' seen as expected (LSA bug fixed, courtesy M. Lamont)
 - Moving from the half-integer resonance \rightarrow 300+ turns (still no RF capture)



- LSA Settings (= deviation from reference): $\Delta Q_H = -0.05$, $\Delta Q_V = -0.2$






- Tune trim vs. measurement fits (w.r.t. $Q_x=0.32$ & $Q_y=0.28$):
 - Horizontal correlation: $\Delta Q_x = (0.96 \pm 0.16) \cdot Q_x(\text{trim}) + (0.03 \pm 0.03)$
 - Vertical correlation: $\Delta Q_y \approx X \cdot Q_x(\text{trim}) + 0.16$
 - Scaling 'X' off due to QD polarity error (fixed by Mike the same day)
- N.B. significant discrepancy in between individual data sets
- 'Space Domain' commissioning of feedback control loop (RealTime & TuneViewer)
 - time-domain pending (quadrupole circuit time constants, etc.)

Present Commissioning State

... lots of first: coupling measurement



- Measured coupling $|C_-| \approx 0.07$
 - Compatible with the assumed magnetic field error model at that time (0.06)



- Coupling wasn't corrected though...
 - Needed for nominal injection tunes ($Q_x = 0.28$, $Q_y = 0.31$)

Present Commissioning State ... Tune Phase-Locked-Loop Commissioning



- ... made the best of the absence of beam in the LHC → used the LHC-PLL installation in the SPS for further tests
 - same interfaces/controls/server/operational GUI as LHC
 - Verified Beam-Transfer-Function (BTF) measurement and PLL logic



- To be tested: real-time display for PLL, LHC-RF interfaces (radial modulation)
- Since BBQ HW is fine for B2 (B1) and that the logic is correct (SPS test): remaining PLL commissioning should take less than one shift/beam.

Chromaticity via Injection vs. Circulating Tune Shift

- Continuous radial modulation (trim) was not fully available/commissioned
- Re-use measured SPS-to-LHC injection energy mismatch !?
 - Measured tune shifts 2009-09-12 (inj. 01:03:52 & circ.: 02:17:46)
 - $\Delta Q_x = +0.006$ & $\Delta Q_y = +0.014$
 - ΔQ & side-bands incompatible with earlier meas. $\Delta p/p \approx 10^{-3}$ (2008-09-10)
 - details on sector-to-sector difference and evolution over time → Jorg



- Some comments on Q' , modulation index and tune width of the BTF

- Turn-by-turn oscillations can be approximated by (n: turn)


$$\Delta z(n) = z_0 \cdot \sin \left(2\pi \cdot \left[Q_0 \cdot n + \frac{Q'}{\omega_s} \frac{\Delta p}{p} \cdot \sin(\omega_s n) \right] + \varphi_\beta \right)$$

$$\cos(\omega_c t + B \sin(\omega_m t)) = \sum_{n=-\infty}^{+\infty} J_n(B) \cdot \cos((\omega_c + n \omega_m) t)$$



- Tune/ Q_s side-band amplitude (J_n : Bessel f.):

$$S_n(Q') = J_n \left(\frac{Q'}{\omega_s} \frac{\Delta p}{p} \right)$$

- linear over a wide range of Q'
- However: Q_s not always visible
→ only upper limits in this case
- Simple estimates for non-linearities
 - ω_s : direct spectra observable
 - $\Delta p/p \approx 10^{-3}$: from bunch RF length (courtesy T.Bohl)




- 2008-09-12 (01:03++)
 - $Q_s = 70 \pm 2 \text{ Hz}$ ($f_{\text{rev}} = 400.788963 \text{ Mhz}$, $U_T = 8 \text{ MV}$)
 - Estimates: $Q'_H \approx Q'_V \approx 34$
 - Settings: $Q'_H = 2.0$, $Q'_V = -30$
 - Asymmetry due to amplitude detuning anti-symmetric (left/right avg.)
 - ~ consistent over several injections
 - N.B. AB-RF found Q_s to be 60 Hz (difference unclear, same spectra)
- changed drastically from Thursday to Friday (machine was magnetically recycled)
- Injection mismatch fit:
 - Injection mismatch is likely $< 10^{-4}$
 - Compatible with above Q' estimates and observed tune shifts (previous slides)
 - further analysis pending (SDDS data)



Beam 2 - Typical Circulating Beam Spectra

- Horizontal and vertical tunes were usually seen without further excitation
 - Typical signal-to-noise: 10-20 dB
 - FFT1 (continuous system, logging) was slightly more sensitive (+ ~ 5 dB)
 - Sufficient for monitoring & steering for the given beam configuration (single pilot)



- Actually, this was a bit of a surprise...

LHC Beam Noise & BBQ Resolution Estimate

- Difference

- $S/N_H \approx 36$ dB, $S/N_V \approx 42$ dB (16382 turns)

- **FWHM $\approx 0.0007 \rightarrow$ Amplification = 227**

- $Q'_H \approx Q'_V < 12$

- Damper kicker (2.5% of 2 μ rad @450GeV)

- Hor. tune amplitude $\approx 185 \mu$ m

- Ver. tune amplitude $\approx 200 \mu$ m

- BBQ noise floor estimates ($2 \cdot 10^9$ p/bunch):

- horizontal: $< 3 \mu$ m

- vertical: $< 2 \mu$ m

- **Residual tune oscillations (quite large):**



- horizontal: $\approx 30 \mu$ m (sources?)


- vertical: $\approx 15 \mu$ m (sources?)

- Note: BBQ resolution scales with bunch intensity (1^{st} order)

- noise floor expected to be ≤ 10 nm for nom. bunches (based on SPS exp.)

- N.B. Need to correlate this with absolute BPM amplitudes







No obvious time structure from one injection to the next
→ dominated by the 'white noise' floor of the BPM acquisition electronic

Residual min/max trajectory drift is compatible with BPM noise estimate (see below).

r.m.s. turn-by-turn noise: $\approx 200 \mu\text{m}$
• as expected from lab and electronic design for the given intensity ($2 \cdot 10^9$ protons/bunch)


- Found 2 (B1)/ 12(B2) polarity/mapping errors – fixed immediately once spotted
- no additional erroneous BPMs found with circulating beam (injection test paid off)

- Residual injection orbit stability (orbit feedback/radial loop off)



- Effective LHC B2 orbit stability about 5 μm \rightarrow understood (next slide)
- Small oscillations/drifts in point 2 and 4 \rightarrow also understood (next slide)


- Effective LHC B2 orbit stability about 6 μm , two known sources:
 1. turn-by-turn noise prediction \rightarrow orbit r.m.s.: $\approx 6 \mu\text{m}$ (150-200 μm , 1024 turns average)
 - However: should be the same for all arc BPMs (same aperture)
 2. Residual noise of the COD power supplies, expectation: 5-10 μm orbit r.m.s.
- **Small drifts in point 2 and 4 \rightarrow thermal drifts (switched off SX4 climatisation)**
 - Known from earlier lab measurements
 - Fix: 'somebody' gets a scarf for Christmas & local crate temperature control



- Exact source of the transient orbit spikes is unknown
 - lasts up to two seconds
 - \rightarrow too slow for an BPM electronics related spike (visible on the whole LHC)
 - (maybe) too fast for COD power-converter transients
 - a forgotten injection/tune/...? kicker magnet?

- ..at two culprits, one in IR2 the other in IR8 (betatron-oscillation beating)

N.B. appears to be triggered by the SPS super cycle



- Some likely but excluded sources:
 - individual CODs: fit requires too many sources to explain the seen pattern
 - Injection septa: only one per beam and either in IR2 or IR8 (B2!)

- **Base-line FFT tune acquisition commissioned for B2**
 - used to establish circulating beam
 - tested polarities, gains, timing, all detectors alive
 - tested RF damper polarities, rough amplitude calibration
 - Now LHC's baseline exciter for Q measurements
 - tested semi-automatic Q and Q' correction schemes (via LSA)
 - tested MKQ trigger & kicker response (synchro-delay adjustments pending)

- **BPMs/Orbit Feedback:**
 - good BPM readings, permitting fast commissioning of circulating beam
 - practically all BPM triggered with intensities down to $\approx 2 \cdot 10^9$ protons
 - noise floor: COD power supplies (5-10 μm), residual BPM 'white noise' (6 μm), thermal BPM drifts ($\sim 35 \mu\text{m}/^\circ\text{C}$, to be fixed)
 - Only few calibration & mapping errors found after injection tests!
 - We are lucky and should probably play the lottery more often!
 - Few noisy pick-ups electronic chains remain to be check/replaced
 - Data concentration and error/fault filter operational
 - Commissioned/tested about 250/1060 CODs with beam (ongoing)

- Full commissioning of B1 FFT1 & FFT2 BBQ systems
 - first turn works (all detectors alive), plane pending
 - otherwise same procedure as for B2:
 - damper polarities, amplitude calibration, ...
- Full commissioning of B1 and B2 BBQ Phase-Locked-Loop Systems
 - pre-requisite for first ramp! However: if no surprises: < shift/beam
- Test of (semi-) automated Q' & C- measurement and correction procedures
 - after SPS tests: LHC-RF radial modulation
- Feedbacks
 - 750/1060 COD polarity and optic checks with beam pending
 - Quadrupole & sextupole circuit mapping/polarity checks with beam
 - test of > 1300 power-converter real-time inputs (AB/PO)
 - Semi- (or even fully) automated FB on Q/C- is probably fastest/easiest to setup
- Training of LHC operators & EIC's
 - (ongoing, some have never seen/measured/corrected Q/Q' and even less C-)



Merry Christmas and a Happy New Year!!!

LHC B2 Commissioning of Q, C- & Q', Ralph.Steinhausen@CERN.ch, 2008-11-27




2008 and initial LHC commissioning were fun...
Thanks a lot for this and see you in 2009!

additional supporting slides

BI's Wall-Current and Head-Tail Monitor



- Tested that detectors are alive and trigger on given timing event
 - Some software tests/adjustments pending
 - one full acquisition presently results in about 1 GByte of data
 - optimisations in the pipe-line
 - optimised memory usage (Java/JDataViewer)
 - optimised/simplified GUI for the WCM
 - Otherwise: same functionality/state as SPS Head-Tail system (bunch length, intensities, HT modes, chroma estimates, ...)



LHC Beam Position Monitor – LHC Day 1

The LHC BPM System at It's Best I/II

LHC B2 Commissioning of Q, C- & Q', Ralph.Steinhausen@CERN.ch, 2008-11-27








LHC Beam Position Monitor – LHC Day 1

The LHC BPM System at It's Best III/II

Could reconstruct LHC B1 optic on the few 10% level using only 50 turns



- Nearly all BPM triggered and gave useful readings
 - LSA concentrator hick-ups relying on FIFO read-out using
- Vertical beta-beat (blue) vs. model (pink)
 - Surprisingly large: 100%
 - further analysis/correction proposal pending (R. Tomas)



LHC B2 Commissioning of Q,C- & Q', Ralph.Steinhaegen@CERN.ch, 2008-11-27

LHC Orbit Feedback Controller & Service Unit

- Tested data concentration of 120 front-end systems, mapping, etc....
 - Worst case latencies shown to be less than 20 ms (small cross-talk with LSA's CMW-get call)
- Tested first-order BPM error/fault detection scheme
- Now default data source for YASP (orbit, CODs, statuses) and 100k turn GUI (statuses)
- Example: B2 sector test – beam as seen/published by the OFC

